

# Request for Board of Commissioners' Action

From: Faye Hughes, County Administrator Date: 7/26/2018

Subject: Road Scores for proposed resurfacing Item Number: VIII - A

Attached is the list of road scores performed by Larry Sanders with his comments. Below I have listed the roads beginning with the highest score (i.e., most deteriorated).

\_\_\_\_ 9.25 Daniel Hesters Rd.  
\_\_\_\_ 9.00 Joiner Rd  
\_\_\_\_ 8.75 Daughtrey Rutland Rd  
\_\_\_\_ 8.25 Reed Bingham Park Rd  
\_\_\_\_ 8.25 Hutchinson Parrish Rd. (East)  
\_\_\_\_ 8.00 Ed Lindsey Rd  
\_\_\_\_ 8.00 Springhill Rd (paved portion)  
\_\_\_\_ 8.00 Evergreen Church Rd (south end)  
\_\_\_\_ 7.75 Michael Dr., Debbie Dr., Westover Dr. (West Acres Subdivision)  
\_\_\_\_ 6.50 Sparks Cutoff Rd  
\_\_\_\_ 6.00 Shady Grove Rd

**Chair will need a motion instructing Larry Sanders to prepare documents and estimates for bidding on roads chosen by Board including:** \_\_\_\_\_

Motion made by \_\_\_\_\_ Second made by \_\_\_\_\_

Discussion: \_\_\_\_\_

\_\_\_\_\_

Votes \_\_\_\_\_ yes \_\_\_\_\_ no

Motion carried/ failed

Score	Road Name / Need
9.25	<b>Daniel Hesters Rd</b> - Road is beyond patching and repairing at this point. Mill asphalt in place and mix in base with soil cement.
9	<b>Joiner Rd</b> - Mill and mix in place with Soil Cement
8.75	<b>Daughtry Rutland Rd</b> - There is noticeable rutting throughout. We will need to level and resurface the entire road. There are a few random stretches that have bad soils. We will need to mill the asphalt and mix in place with soil cement to repair these areas.
8.25	<b>Reed Bingham Park Rd</b> - Base is in pretty good shape with minimal to moderate patching necessary. Patch, Level, and Resurface.
8.25	<b>Hutchinson Parrish Rd (East End)</b> - Mill and Mix in place the stretch of road adjacent to the Country Club. Patch, Level, and Resurface the remainder.
8	<b>Ed Lindsey Rd</b> - Pot Holing is not excessive but there is a thin lift of surface treatment over the original surface that is beginning to break free. As soon as practical We need to level and resurface with minimal pot hole repairs.
8	<b>Springhill Rd</b> - Level and Resurface with miscellaneous patching
8	<b>Evergreen Church Rd (South end)</b> - Moderate to excessive patching along edges.
7.75	<b>Michael Dr., Debbie Dr., and Westover Dr. (West Acres Subdivision)</b> - Patch and Resurface.
6.5	<b>Sparks Cutoff Rd</b> - Road is holding up fairly well. We could patch this road and hold off until later to level and resurface.
6	<b>Shady Grove Rd</b> - Road is in pretty good shape.