Tim Cannington Construction, Inc.

Estimate

P.O. Box 106 Sparks, GA 31647 229-251-5867 email 10cann@gmail.com

Date	Estimate #	
10/3/2022	651	

COOK COUNTY.
ATTN:DWIGHT PURVIS
RE: CONCRETE WORK
email:hayman4750@yahoo.com

Project		

Item	Description	Total
Service	RETENTION WINGS AND WATER FLOW OUTLET (2) 16' LONG X 8' TALL WING WALLS 12" THICK 4000 PSI DOUBLE REBAR REINFORCED \$10,400 EACH WING WALL	20,800.00
Service	(2) 17' LONG FOOTINGS 3' WIDE 2' THICK 4000 PSI TRIPLE REBAR REINFORCED \$9,300 EACH FOOTING	18,600.00
Service	(1) 24' X 8' SPLASH PAD 24' X 2' UNDERMINING FOOTING 6" THICK 4000 PSI REBAR REINFORCED	5,500.00
Service	(1) LOAD RIPRAP INSTALLED	4,000.00
Service	PRICE INCLUDES LABOR AND MATERIALS	

Thank You For Your Business!!	Total	\$49,000,00
Tim Cannington	Total	\$48,900.00